



SUPPLEMENTAL/ BID BULLETIN NO. 1

IB2024 – 087E
PROCUREMENT OF PROPOSE REPAIR AND RENOVATION OF M DELA CRUZ,
PASAY CITY

This Supplemental/Bid Bulletin No. 1 is being issued to revise provisions/specifications in the Bidding Documents for a forecited project:

1. Query during Pre-bidding Conference:		
Technical Specifications	Query	Response of the End User Unit
List of contractor Key Personnel	Submission of different set of names in the list of Contractor's Personnel per project	Submission of different set of names in the list of Contractor's Personnel per project NOT GRANTED
List of Equipment -	Submission of different set of names of equipment per project	Submission of different set of names of equipment per project NOT GRANTED

Bidders are advised to use the **following attached forms and submit them together with all required documents for the submission of bids on the 25th day of October 2024, 9:00 AM:**

This Supplemental/Bid Bulletin No. 1 shall be integral to the Bidding Documents. All other provisions indicated in the bidding documents not affected by this Supplemental/Bid Bulletin No. 1 shall remain in effect.

For guidance and information of all concerned.

Issued this 18th day of October 2024 in MMCHD

Approved by:


JEREMIAS FRANCIS Y. CHAN, MD
Licensing Officer V / BAC Chairperson

Republic of the Philippines

Department of Health

Metro Manila Center for Health Development

Technical Specifications

Item No. 1	PROCUREMENT OF PROPOSE REPAIR AND RENOVATION OF M DELA CRUZ	Qty./Unit	1 LOT		
ABC: 4,998,361.66					
PURCHASER'S SPECIFICATION		STATEMENT OF COMPLIANCE			
BILL OF QUANTITIES					
Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center					
ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
PART I	GENERAL REQUIREMENTS				
B.5(1)	Project Billboard / Signboard	1.00	ea./hr.		
B.7(1)	Occupational Safety and Health Program	1.00	L.S		
a.	Personal Protective Equipment (PPE):				
b.	Safety Shoes (different sizes)				
c.	Safety helmet/ Hard hat (free size)				
d.	Working Gloves (free size)				
e.					
f.					

Lease of Equipment - for clarification (all items)

g.	Vest				
h.	Rain Coats				
i.	Dust Mask				
j.	Eye Goggles				
a.	Ear Muff				
b.	Body Harness				
	Rubber Boots				
	Antispetics and Disinfectant				
	Ethyl Alcohol				
	Liquid and Soap				
B.9	Mobilization/Demobilization	1.00	L.S		
B.24	General Scaffolding and Shoring	1.00	L.S		
a.	Scaffoldings				
b.	H-frame 1.7 m x 1.2 m, set				
c.	H-frames				
d.	diagonal cross braces				
e.	horizontal braces				
f.	joint pins				
g.	Shoring Jack, 3.8 m full extension				
h.	Adjustable, U-head Jack, 0.6 m				
i.	Adjustable, Base Jack, 0.6 m				
j.	1-1/2" GI Pipe x 6.0 m				
k.	1-1/2" GI Pipe x 3.0 m				
l.	1-1/2" GI Pipe x 4.0 m				
m.	1-1/2" GI Pipe x 1.0 m				
n.	Tie Rod x 0.60 m				
	Round Wing Nut				
	TOTAL OF PART I				

PART II	DEMOLITION WORKS				
801 (1)	Removal of Structures & Obstruction	1.00	L.S		
	TOTAL OF PART II				
PART III	CONCRETE WORKS				
900 (1)	Structural Concrete (Class A, 28 Days)				
a.	GRAVEL G3/4	4.00	CUM		
b.	FINE AGGREGATE	2.00	CUM		
c.	PORTLAND CEMENT	32.00	BAG		
902 (1)	Reinforcing Steel of Reinforced Concrete Structures (Grade 40)				
a.	REINFORCING STEEL BARS DEFORMED GRADE 40	266.00	KG		
b.	GI TIE WIRE #16	4.00	KG		
c.	Miscellaneous (cutting disc, chalk stone, etc.)	1.00	l.s		
903 (2)	Formworks and Falseworks	1.00	l.s		
1020(3)	Floor Topping				
a.	PORTLAND CEMENT	9.00	BAG		
b.	FINE AGGREGATE	1.00	CUM		
	TOTAL OF PART III				
PART IV	MASONRY WORKS				

1046	150mm thk CHB Non Load Bearing (Including Reinforcing Steel)				
a.	CHB ORDINARY (150mm x 203mm x 406mm)	355.00	PC		
b.	PORTLAND CEMENT	41.00	BAG		
c.	FINE AGGREGATE	1.25	CUM		
d.	REINFORCING STEEL BARS PLAIN GRADE 40	89.00	KG		
e.	GI TIE WIRE #16	1.50	KG		
1046a	100mm thk CHB Non Load Bearing (Including Reinforcing Steel)				
a.	CHB ORDINARY (101mm x 203mm x 406mm)	1,359.00	PC		

Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
b.	PORTLAND CEMENT	55.00	BAG		
c.	FINE AGGREGATE	4.25	CUM		
d.	REINFORCING STEEL BARS PLAIN GRADE 40	339.00	KG		
e.	GI TIE WIRE #16	5.25	KG		
1027(1)	Cement Plaster Finish				
a.	PORTLAND CEMENT	95.00	BAG		
b.	FINE AGGREGATE	8.00	CUM		

	TOTAL OF PART IV				
PART V	TILE WORKS				
1018 (1)	60cm x 60cm Non-skid Ceramic Floor Tiles and Glazed Wall Tiles				
a.	PORCELAIN/ CERAMIC GLAZED TILES	250.00	SQM		
b.	CERAMIC UNGLAZED TILE	74.00	SQM		
c.	PORTLAND CEMENT	101.00	BAG		
d.	FINE AGGREGATE	9.00	CUM		
e.	TILE GROUT, 25KG	39.00	BAG/S		
f.	TILE ADHESIVE, HEAVY DUTY, 25KG / BAG	42.00	BAG/S		
g.	2" Rise, Aluminum, Threshold Ramp	33.00	pc/s		
h.	Miscellaneous (cutting disc, grout sealer, tile spacers, etc.)	1.00	l.s		
1020a	Homogeneous Antibacterial Vinyl Sheet				
a.	HOMOGENEOUS ANTIBACTERIAL VINYL SHEET (200 MMH COVE) INCLUDING, ADHESIVE AND ALL CONSUMABLES	18.90	SQM		
b.	COVE FORMER (38MM RADIUS)	15.00	LNM		
c.	CAPPING STRIP	15.00	LNM		

d.	SELF LEVELING COMPOUND 25Kg/bag	4.00	BAG/S		
	TOTAL OF PART V				
PART VI	CEILING WORKS				
1003 (1)	6mm Fiber Cement Board on Metal Frame Ceiling				
a.	FIBER CEMENT BOARD, 1/4" (6MM) X 4' X 8'	68.00	SHEET/S		
b.	0.50MM THK, 19MM X 50MM X 5M METAL FURRING (DOUBLE)	211.00	PC/S		
c.	0.80MM THK, 12MM X 38MM X 5M CARRYNG CHANNEL	67.00	PC/S		
d.	HANGER BARS/ROD	187.00	PC/S		
e.	CHANNEL CLIP	1,117.00	PC/S		
f.	WALL ANGLE	45.00	PC/S		
g.	RIVETS	2,605.00	PC/S		
h.	1" METAL SCREW	745.00	PC/S		
	TOTAL OF PART VI				
PART VII	ELECTRICAL WORKS				
1102	Panel Board with Main Breaker/Branches, 3 wires, 1 neutral, 50 Amp - 200 Amp				

a.	<p>Main Distribution Panel - MDP</p> <p>MAIN: 80AT, 100AF, 3P MCCB, 230V</p> <p>BRANCH:</p> <p>6 - 20AT, 100AF, 2P, MCB</p> <p>6 - 30AT, 100AF, 2P, MCB</p> <p>In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted</p>	2.00 set			
b.	<p>Main Distribution Panel - MDP</p> <p>MAIN: 80AT, 100AF, 3P MCCB, 230V</p> <p>BRANCH:</p> <p>8 - 20AT, 100AF, 2P, MCB</p> <p>7 - 30AT, 100AF, 2P, MCB</p> <p>In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted</p>	1.00 set			
c.	Miscellaneous (cable ties, electrical tape, terminal lugs, etc.)	1.00	l.s		
1102	Panel Board with Main Breaker/Branches, 3 wires, 1 neutral, 250 Amp - 400 Amp				
<p>Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center</p>					

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
a.	Main Distribution Panel - MDP MAIN: 250AT, 250AF, 3P MCCB, 230V BRANCH: 4 - 80AT, 100AF, 3P, MCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted	1.00	set		
b.	Miscellaneous (cable ties, electrical tape, terminal lugs, etc.)	1.00	l.s		
1103 (1)	Lighting fixtures				
a.	Surface Mounted 32W - 1200x300mm Rectangle LED Light Panel	16.00	sets		
b.	25W, 230mm Ø, Surface Mounted LED Downlight (Daylight)	10.00	sets		
c.	40W, 60cm x 60cm, LED Panel (Daylight)	42.00	sets		
d.	8W, T5, LED Batten (Daylight)	36.00	sets		
e.	6W, Dual-Optic LED Emergency Light	5.00	pcs		
f.	20W, 8" x 8", Ceiling Mount Exhaust Fan (Modern Frame)	11.00	pcs		
1101 (2)	1 mm ² - 5.5 mm ² Electric Wire (TW/THHN/TWHN)				

a.	THHN wire No. 10 (Stranded) 5.5mm ²	2.00	box		
b.	THHN wire No.12 (Stranded - 3.5mm ²)	16.00	box		
c.	THHN wire No. 14 (Stranded - 2.0mm ²)	3.00	box		
d.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1101 (2)	8 mm ² - 22 mm ² Electric Wire (TW/THHN/TWHN)				
a.	THHN wire No. 4 (Stranded - 22mm ²)	185.00	meters		
b.	THHN wire No.6 (Stranded - 14mm ²)	70.00	meters		
c.	THHN wire No. 8 (Stranded - 8.0mm ²)	113.00	meters		
d.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1101 (2)	150 mm ² - 250 mm ² Electric Wire (TW/THHN/TWHN)				
a.	THHN wire No.250 (Stranded - 125mm ²)	113.00	meters		
b.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1100	Junction/Utility/Pull/Square Box				
a.	Junction Box	166.00	pcs		
b.	Utility Box	114.00	pcs		

c.	Electrical Tape (Big)	12.00	pcs		
d.	Cable Tie 3x150mm	10.00	pack		
e.	Miscellaneous (torch, etc.)	1.00	l.s		
1100 (6)	15 mm ² - 32 mm ² - Polyvinyl Chloride (PVC) Pipes				
	a. RSC Pipe 3"Ø (80mmØ)	10.00	pcs.		
	b. PVC Pipe 1"Ø (32mmØ)	26.00	pcs.		
	c. PVC Pipe 1/4"Ø (25mmØ)	12.00	pcs.		
	d. PVC Pipe 1/2"Ø (20mmØ)	173.00	pcs.		
	e. PVC Male Adapter With Locknut 1"Ø (32mmØ)	13.00	pcs.		
	f. PVC Male Adapter With Locknut 3/4"Ø (25mmØ)	6.00	pcs.		
	g. PVC Male Adapter With Locknut 1/2"Ø (20mmØ)	87.00	pcs.		
	h. C- Clamp 1"Ø (32mmØ)	78.00	pcs.		
	i. C- Clamp 1/4"Ø (25mmØ)	35.00	pcs.		
	j. C- Clamp 1/2"Ø (20mmØ)	519.00	pcs.		
	k. Miscellaneous (torch, etc.)	1.00	l.s		
1100 (1)	80mm ² dia. - 100 mm ² dia. Rigid Steel Conduit (RSC)/Intermediate metal Conduit (IMC)/Electrical Metal Tubing (EMT)				
	a. RSC Pipe 3"Ø (80mmØ)	15.00	pcs		

	b. RSC Coupling 3Ø (82mmØ)	8.00	pcs		
	c. C- Clamp 3"Ø (80mmØ)	30.00	pcs		
	d. Miscellaneous (tie wire, torch, etc.)	1.00	l.s		
1101	Duplex Convenience Outlet/Receptacle, Grounding Type (GT) I Weather Proof Duplex Convenience Outlet/Receptacle, Grounding Type (GT)I Special Purpose Convenience Outlet/Receptacle, Grounding Type for ACU, WH, etc./ Explosion Proof Type Duplex Convenience Outlet/Receptacle, Grounding Type (GT)I Duplex Convenience Outlet/Receptacle with Ground Fault Circuit Interrupter				
	a. Two Gang Universal Outlet with Ground with plate w/ Plate	72.00	pcs		
	b. Aircon Outlet with plate	11.00	pcs		

Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
c.	Double Switch w/ Plate	26.00	pcs		
	d. Single Switch w/ Plate	28.00	pcs		

1200	Airconditioning and Refrigeration System				
a.	Supply and installation of 2.0 hp inverter type, wall mounted aircon including steel housing and complete accessories	10.00	set		
	TOTAL OF PART VII				
PART VIII	PLUMBING SYSTEM WORKS				
1001(8)	Installation of Polyvinyl Chloride (PVC) and other fittings				
	a. PVC PIPES (50mm D)	50.00	PC		
	b. PVC PIPES (101mm D)	30.00	PC		
	c. PVC 45deg. (3mm BEND x 101mm)	25.00	PC		
	d. PVC 87.5deg. (6mm BEND x 50mm)	60.00	PC		
	e. PVC 87.5deg. SINGLE BRANCH, SEEP, TEE (101mm x 101mm)	5.00	PC		
	f. PVC 45deg. SINGLE BRANCH, WYE (101mm x 101mm)	15.00	PC		
	g. PVC 45deg. SINGLE BRANCH, WYE (101mm x 50mm)	25.00	PC		
	h. PVC 45deg. SINGLE BRANCH, WYE (50mm x 50mm)	20.00	PC		
	i. BRASS CLEAN-OUT W/ PLUG	3.00	SET/S		

	& SEALING RING -(FLUSH) (50mm)				
	j. BRASS CLEAN-OUT W/ PLUG & SEALING RING -(FLUSH) (101mm)	4.00	SET/S		
	k. PVC 87.5deg. SINGLE BRANCH, SEEP, TEE (101mm x 50mm)	10.00	PC		
	l. PVC 45deg. (3mm BEND x 50mm)	45.00	PC		
	m. PVC TEE (50mm D)	5.00	PC		
	n. PVC P-TRAP W/ PLUG & SEALING RING (50mm)	1.00	PC		
	o. PVC CONCENTRIC BUSHING REDUCER (101mm x 50mm)	5.00	PC		
	p. 1-1/2" Ø SS BOTTLE TRAP	11.00	SET/S		
	q. 1-1/2" Ø uPVC BOTTLE TRAP	5.00	SET/S		
	r. Miscellaneous (400cc solvent cement, teflon tape, sealant, etc.)	1.00	l.s		
1002(3)	Installation of Polypropylene Random Copolymer (PPR) and other fittings				
	a. 3/4" Ø x 4m, PN20, PPR PIPE	20.00	PC/S		
	b. 1/2" Ø x 4m, PN20, PPR PIPE	20.00	PC/S		
	c. 25mm x 25mm x 25mm TEE	1.00	PC/S		

	d. 25mm x 20mm x 25mm TEE	10.00	PC/S		
	e. 20mm x 20mm x 20mm TEE	20.00	PC/S		
	f. 25mm x 90° ELBOW	10.00	PC/S		
	g. 20mm x 90° ELBOW	30.00	PC/S		
	h. 25mm TEE THREADED	1.00	PC/S		
	i. 20mm TEE THREADED	22.00	PC/S		
	j. 20mm END CAP	22.00	PC/S		
	k. 25mm UNION PATENTE MALE	1.00	PC/S		
	l. 25mm COUPLING	5.00	PC/S		
	m. 20mm COUPLING	5.00	PC/S		
	n. 25mm x 20mm BUSHING	5.00	PC/S		
	o. 1/2", PN20, PPR STOP VALVE	14.00	PC/S		
	p. 3/4", PN20, PPR CHECK VALVE	1.00	PC/S		
q.	Miscellaneous (special fusion tool, marker, pipe cutter, sand paper, clean cloth, sleeves, etc.)	1.00	l.s		
1002(5)	Installation of Plumbing Fixtures				

a.	Dual-Flush, Elongated, One-Piece Water Closet including tank fitting, toilet bowl fastener and all other accessories and consumables	4.00	SET		
b.	Wall-Mount Urinal w/ Integral Trap including Lever type Flush Valve and all other accessories and consumables	1.00	SET		
c.	500mm x 400mm x 200mm Undermount, Single-Bowl, SS Sink including SS Gooseneck Faucet accessories and consumables	11.00	SET/S		
d.	Half-Pedestal Lavatory w/ Integral Trap including SS Faucet, SS Angle Valve and all other accessories and consumables	4.00	PC/S		
	e. 10cm x 10cm Square, SS Invisible Floor Drain including consumables	5.00	PC/S		
	f. SS Wall-mount Soap Holder	4.00	PC/S		

Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
	g. SS Wall-mount Tissue Holder	4.00	PC/S		
h.	SS Hand-Held Bidet Spray including SS wall-mount holder and all other accessories and consumables	4.00	PC/S		
	i. SS Wall-Mount Hose Bibb including accessories and	1.00	PC/S		

	consumables				
	j. SS Grab Bar	4.00	PC/S		
	k. Wall Shower Head	1.00	PC/S		
	l. SS Wall-mount Shower Curtain Rod	2.00	PC/S		
	m. SS Wall-mount Towel Rack	1.00	PC/S		
	n. 30" x 36" Frameless Wall- mount Mirror including Mounting Clips	4.00	PC/S		
	TOTAL OF PART VIII				
PART IX	PAINTING WORKS				
1032(1)a	Painting works				
	a. CONCRETE NEUTRALIZER	5.00	LTR		
	b. CONCRETE PRIMER	55.00	GAL/S		
	c. PATCHING COMPOUND	69.00	KG/S		
	d. PAINT LATEX SEMI GLOSS	110.00	GAL		
	e. GLAZING PUTTY	3.00	GAL/S		
	f. FLAT WALL ENAMEL	3.00	GAL/S		
	g. QUICK DRY ENAMEL	3.00	GAL/S		
	h. THINNER PAINT	25.00	GAL		
	i. TINTING COLOR	1.00	PINT		
	j. PAINT METAL EPOXY	2.00	GAL/S		

	k. PAINT ENAMEL	4.00	GAL/S		
i.	Miscellaneous (Air brush, paint roller with tray, paint brush, tinting & acry colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
	TOTAL OF PART IX				
PART X	DOOR AND WINDOWS				
1006	Steel Doors and Frame with complete accessories				
a.	GA. 18 Aluminum Louvered Door on GA 16 50mm x 75mm baked powder coated with stainless barrel bolt and stainless steel handle and provide foot & chain bolts				
1	1 set/s - 1.6mW x 2.10mH; 2 Panel Steel Louvered Door; (1 Panel door 0.8mL x 2.10mH) Lockset: 2 unit/s C-type pull handle, 1 unit/s deadbolt, 8 pc/s heavy duty s/s hinges, and 1 pc/s s/s barrel bolt 3/4" x 12"	3.36	m ²		
	Location: GF - Pump Room				
b.	Salvageable Grille Door (1set/s Exit Door near TB-DOTS) - including removal and reinstallation, replacement of damaged frames & hinges, locking mechanism, surface preparation, repainting using airbrush tool				

1	1 set/s - 0.90mW x 2.10mH Grille door	1.89	m ²		
c.	Salvageable Roll up Door (1set/s Main Entry) - repair				
1	1 set/s - 1.40mW x 2.10mH Roll Up Door	2.94	m ²		
d.	Miscellaneous (Air brush, paint roller with tray, paint brush, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1007	Aluminum Glass Door (Sliding Type/ Swing Type)				
a.	12mm thk Tempered clear glass on 50mm x 100mm analok aluminum frame on 50mm x 100mm analok aluminum door jamb, complete with accessories				
1	1 set/s - 1.4mW x 2.15mH Double Swing Glass Door; 1 Panel door (0.65mL x 2.10mH) with fixed glass transom (1.40mL x 0.40mH) Lockset: 2 unit/s C-type pull handle, 1 set locking mechanism (double finish round cylinder with lock case), 4 pc/s heavy duty pivot hinges and floor door lock	2.94 m ²			
b.	Refurbishing of Main Access Door,				
1	1 set/s - 1.4mW x 2.15mH Double Swing Glass, Lockset: 2 unit/s C type pull handle, 1 set locking mechanism (double finish round	2.94	m ²		

	cylinder with lock case), 4 pc/s heavy duty pivot hinges and floor door lock				
--	--	--	--	--	--

Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
c.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1008	Aluminum Glass Window (Sliding/ Casement / Awning/ Fixed Type)				
a.	AWNING TYPE STEEL CASEMENT WINDOWS, WHITE	0.30	m ²		
1	1 set/s - 0.6.mW x 0.5mH; 1 Panel Awning Window				
	Location: GF - Sputum Collection				
b.	SLIDING ALUMINUM WINDOW, WHITE	10.56	m ²		
1	1 set/s - 0.80mW x 1.60mH; 2 Track Sliding Window				
	Location: GF -Storage Room				
2	1 set/s - 0.80mW x 1.20mH; (0.8mH Fixed Window); (0.4mH - 2 Track Sliding/ pass-through Window)				
	Location: GF -Sputum				

	Collection				
3	3 set/s - 1.20mW x 1.60mH; 2 Track Sliding Window				
	Location: GF -TB DOTS, 2ND FLR- Collection Room, Adolescent Room				
4	1 set/s - 1.60mW x 1.60mH; 2 Track Sliding Window				
	Location: GF -Admission Area				
c.	Salvageable Window (2set/s) - including removal and reinstallation, replacement of damaged frames, resealant, surface preparation, repainting using airbrush tool	2.70	m ²		
1	1 set/s - 0.60mW x 0.50mH; 1 Panel Awning Window				
2	1 set/s - 1.50mW x 1.60mH				
d.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1010(2)b	Wooden Panel Door				
a.	FLUSH TYPE SOLID CORE DOOR ON 50MM x 75MM WOODEN DOOR JAMB	7.14	m ²		
1	1 set/s - 1.20mW Door with (0.40mW x 2.10mH and 0.80mW x 2.10mH) - 2 Panel Solid Core Flush Door				
	Location: GF - Minor Surgical Room				

2	1 set/s - 0.80mW x 2.10mH - 1 Panel Solid Core Flush Door				
	Location: 2nd Flr - Collection room				
3	2 set/s - 0.70mW x 2.10mH - 1 Panel Solid Core Flush Door				
	Location: GF - 2 set/s at File Storage				
b.	Salvageable Door (12 set/s) - refurbishing of 0.90mW x 2.10mH Solid Core Flush Door including removal and reinstallation, surface preparation, repainting using airbrush tool	22.68	m ²		
1	0.90mW x 2.10mH Solid Core Flush Door				
c.	DOOR LOCKS	16.00	SET		
d.	HINGE (50mm x 101mm)	51.00	PR		
e.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, etc.)	1.00	l.s		
1043	PVC Door and Frames with complete accesories				
a.	PVC DOOR ON 50MM x 75MM PVC DOOR JAMB	7.35	m ²		
	1 1 set/s - 0.90mW x 2.10mH PVC Door with louver				
	Location: GF - PWD CR				

	2 2 set/s - 0.70mW x 2.10mH PVC Door with louver				
	Location: 2nd flr - Staff Toilet and Patient Toilet				
	3 2 set/s - 0.60mW x 2.10mH PVC Door with louver				
	Location: GF - Staff Toilet and Janitors Closet				
	b. DOOR LOCKS	5.00	SET		
	c. HINGE (50mm x 101mm)	15.00	PR		
	e. Miscellaneous (sealant, etc.)	1.00	l.s		
	TOTAL OF PART X				
PART XI	PROVISIONAL ITEMS				
1016	Waterproofing Cement Base				
	a. WATER PROOFING CEMENT	4.00	BAG		
Z.1	Provision of Epoxy Paint Finish				
a.	EPOXY PRIMER	1.00	GAL/S		
b.	EPOXY REDUCER	1.00	GAL/S		

Project Title: Proposed Repair and Renovation of M Dela Cruz Health Center

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
c.	AQUA EPOXY	2.50	GAL/S		
d.	Miscellaneous (paint roller with tray, paint brush, tinting colors, stopa rugs, sand paper, etc.)	1.00	l.s		
Z.2	Provision of dismantling and reinstallation of existing cabinets				
a.	SEALANT	5.00	CRTG		
b.	Miscellaneous (caulking gun, sponge, caulk tool, painter's tape, etc.)	1.00	l.s		
Z.3	Provision of Canopy				
a.	TEK SCREW	60.00	PC		
	b. 3.0MM THK X 4' X LN.FT. CLEAR POLYCARBONATE SOLID PANEL	14.00	LN.FT.		
	c. Miscellaneous (sealant, etc.)	1.00	l.s		
Z.4	Provision of 12" Height SS Embossed Text Signage and 800mm Ø SS Embossed Circular Logo Signage	1.00	L.S.		
a.	12" Height SS Embossed Text Signage	21.00	PC/S		
	(' M DELA CRUZ HEALTH				

	CENTER ')				
b.	800mm Ø SS Embossed Circular Logo Signage (Pasay Health Department Seal)	1.00	PC/S		
c.	Miscellaneous (sealant, etc.)	1.00	l.s		
Z.5	Provision to refurbish the existing windows, such as resealing, replacement of locking mechanism and hinges	1.00	l.s		
Z.6	Provision to relocate the watertank into the proposed pump room	1.00	l.s		
	TOTAL OF PART XI				
PART XII	CABINETS WORKS				
1003(3)	Cabinets				
a.	Marine Plywood (1.2m x 2.4m x 19mm)	30.00	pc		
b.	Marine Plywood (1.2m x 2.4m x 6mm)	5.00	pc		
c.	Particle Board with laminates on 2 sides, 3/4" (19mm) x 4' x 8'	5.00	sheet/s		
d.	Bar, GI, Tubular, 1.2mm x 1" x 1" x 6m	4.00	pc/s		
e.	S4S KD Lumber 1" x 2" x 12ft	2.00	pc/s		
f.	PVC 3/4" Edging	40.00	ln.m		

g.	2" x 4" x 10' s4s KD	5.00	pc		
h.	1" x 2" x 10' s4s KD	20.00	pc		
i.	1/2" x 1" x 10' s4s KD	100.00	pc		
j.	Handle door	50.00	pc		
i.	Soft Closed Concealed Hinges	100.00	pr		
j.	Wellwood Glue	5.00	gal		
k.	Assorted Common Wire Nails	5.00	kg		
l.	Concrete Nails (3")	5.00	kg		
m.	Sandpaper	1.00	roll		
n.	Miscellaneous (wood glue, nail, etc.)				
	TOTAL OF PART XII				
	GRAND TOTAL				
*Including all Direct and Indirect Cost per Items.					

