



Republic of the Philippines
DEPARTMENT OF HEALTH
Metro Manila Center for Health Development



SUPPLEMENTAL/ BID BULLETIN NO. 1

IB2024 – 088E
PROCUREMENT OF PROPOSE REPAIR AND RENOVATION OF KALAYAAN
HEALTH CENTER, PASAY CITY

This Supplemental/Bid Bulletin No. 1 is being issued to revise provisions/specifications in the Bidding Documents for a forecited project:

1. Query during Pre-bidding Conference:		
Technical Specifications	Query	Response of the End User Unit
List of contractor Key Personnel	Submission of different set of names in the list of Contractor's Personnel per project	Submission of different set of names in the list of Contractor's Personnel per project NOT GRANTED
List of Equipment -	Submission of different set of names of equipment per project	Submission of different set of names of equipment per project NOT GRANTED

Bidders are advised to use the **following attached forms and submit them together with all required documents for the submission of bids on the 25th day of October 2024, 9:00 AM:**

This Supplemental/Bid Bulletin No. 1 shall be integral to the Bidding Documents. All other provisions indicated in the bidding documents not affected by this Supplemental/Bid Bulletin No. 1 shall remain in effect.

For guidance and information of all concerned.

Issued this 18th day of October 2024 in MMCHD

Approved by:


JEREMIAS FRANCIS Y. CHAN, MD
Licensing Officer V / BAC Chairperson

BILL OF QUANTITIES

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
PART I	GENERAL REQUIREMENTS				
B.5(1)	Project Billboard / Signboard	1.00	ea./hr.		
B.7(1)	Occupational Safety and Health Program Personal Protective Equipment (PPE): a. Safety Shoes (different sizes) b. Safety helmet/ Hard hat(free size) c. Working Gloves (free size) d. Vest e. Rain Coats f. Dust Mask g. Eye Goggles h. Ear Muff i. Body Harness j. Rubber Boots a. Antispetics and Disinfectant Ethyl Alcohol b. Liquid and Soap	1.00	L.S		
B.9	Mobilization/Demobilization	1.00	L.S		
B.24	General Scaffolding and Shoring Scaffoldings a. H-frame 1.7 m x 1.2 m, set b. H-frames c. diagonal cross braces d. horizontal braces e. joint pins f. Shoring Jack, 3.8 m full extension g. Adjustable, U-head Jack, 0.6 m h. Adjustable, Base Jack, 0.6 m i. 1-1/2" GI Pipe x 6.0 m j. 1-1/2" GI Pipe x 3.0 m k. 1-1/2" GI Pipe x 4.0 m l. 1-1/2" GI Pipe x 1.0 m m. Tie Rod x 0.60 m n. Round Wing Nut	1.00	L.S		
	TOTAL OF PART I				
PART II	DEMOLITION WORKS				
801 (1)	Removal of Structures & Obstruction	1.00	L.S		
	TOTAL OF PART II				
PART III	CONCRETE WORKS				
900 (1)	Structural Concrete (Class A, 28 Days)				
a.	GRAVEL G3/4	12.00	CUM		
b.	FINE AGGREGATE	6.00	CUM		
c.	PORTLAND CEMENT	105.00	BAG		
902 (1)	Reinforcing Steel of Reinforced Concrete Structures (Grade 40)				
a.	REINFORCING STEEL BARS DEFORMED GRADE 40	551.00	KG		
b.	GI TIE WIRE #16	8.25	KG		

c.	Miscellaneous (cutting disc, chalk stone, etc.)	1.00	l.s		
903 (2)	Formworks and Falseworks	59.36	m ²		
1020(3)	Floor Topping				
a.	PORTLAND CEMENT	52.00	BAG		
b.	FINE AGGREGATE	4.25	CUM		
	TOTAL OF PART III				
PART IV	MASONRY WORKS				
1046	150mm thk CHB Non Load Bearing (Including Reinforcing Steel)				
a.	CHB ORDINARY (150mm x 203mm x 406mm)	205.00	PC		
b.	PORTLAND CEMENT	24.00	BAG		
c.	FINE AGGREGATE	0.75	CUM		
d.	REINFORCING STEEL BARS PLAIN GRADE 40	52.00	KG		
e.	GI TIE WIRE #16	1.00	KG		
1046a	100mm thk CHB Non Load Bearing (Including Reinforcing Steel)				
a.	CHB ORDINARY (101mm x 203mm x 406mm)	5310.00	PC		

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
b.	PORTLAND CEMENT	215.00	BAG		
c.	FINE AGGREGATE	16.50	CUM		
d.	REINFORCING STEEL BARS PLAIN GRADE 40	1324.00	KG		
e.	GI TIE WIRE #16	21.00	KG		
1027(1)	Cement Plaster Finish				
a.	PORTLAND CEMENT	313.00	BAG		
b.	FINE AGGREGATE	26.00	CUM		
	TOTAL OF PART IV				
PART V	TILE WORKS				
1018 (1)	60cm x 60cm Non-skid Ceramic Floor Tiles and Glazed Wall Tiles				
a.	PORCELAIN/ CERAMIC GLAZED TILES	336.00	SQM		
b.	CERAMIC UNGLAZED TILE	82.00	SQM		
c.	GRANITE SOLID SURFACE COUNTER TOP	68.00	SQM		
d.	PORTLAND CEMENT	150.00	BAG		
e.	FINE AGGREGATE	12.00	CUM		

f.	TILE GROUT, 25KG	58.00	BAG/S		
g.	TILE ADHESIVE, HEAVY DUTY, 25KG / BAG	63.00	BAG/S		
h.	2" Rise, Aluminum, Threshold Ramp	33.00	pc/s		
i	Miscellaneous (cutting disc, grout sealer, tile spacers, etc.)	1.00	l.s		
1020a	Homogeneous Antibacterial Vinyl Sheet				
a.	HOMOGENEOUS ANTIBACTERIAL VINYL SHEET (200 MMH COVE) INCLUDING, ADHESIVE AND ALL CONSUMABLES	108.00	SQM		
b.	COVE FORMER (38MM RADIUS)	95.00	LNМ		
c.	CAPPING STRIP	95.00	LNМ		
d.	SELF LEVELING COMPOUND 25Kg/bag	24.00	BAG/S		
	TOTAL OF PART V				
PART VI	CEILING WORKS				
1003 (1)	6mm Fiber Cement Board on Metal Frame Ceiling				
a.	FIBER CEMENT BOARD, 1/4" (6MM) X 4' X 8'	122.00	SHEET/S		
b.	0.50MM THK, 19MM X 50MM X 5M METAL FURRING (DOUBLE)	376.00	PC/S		
c.	0.80MM THK, 12MM X 38MM X 5M CARRYNG CHANNEL	119.00	PC/S		
d.	HANGER BARS/ROD	333.00	PC/S		
e.	CHANNEL CLIP	1993.00	PC/S		
f.	WALL ANGLE	80.00	PC/S		
g.	RIVETS	4652.00	PC/S		
h.	1" METAL SCREW	1329.00	PC/S		
	TOTAL OF PART VI				
PART VII	ELECTRICAL WORKS				
1102	Panel Board with Main Breaker/Branches, 3 wires, 1 neutral, 50 Amp - 200 Amp				
a.	Main Distribution Panel - MDP MAIN: 60AT, 100AF, 3P MCCB, 230V BRANCH: 12 Branches 7 - 20AT, 100AF, 2P, MCB 5 - 30AT, 100AF, 2P, MCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted	1.00	set		
b.	Main Distribution Panel - MDP MAIN: 100AT, 100AF, 3P MCCB, 230V BRANCH: 14 Branches 6 - 20AT, 100AF, 2P, MCB 8 - 30AT, 100AF, 2P, MCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted	1.00	set		

c.	Main Distribution Panel - MDP MAIN: 60AT, 100AF, 3P MCCB, 230V BRANCH: 14 Branches 6 - 20AT, 100AF, 2P, MCB 6 - 30AT, 100AF, 2P, MCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted	1.00	set		
----	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	-----	--	--

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
c.	Miscellaneous (cable ties, electrical tape, terminal lugs, etc.)	1.00	l.s		
1102	Panel Board with Main Breaker/Branches, 3 wires, 1 neutral, 250 Amp - 400 Amp				
a.	Main Distribution Panel - MDP MAIN: 300AT, 300AF, 3P MCCB, 230V BRANCH: 1 - 100AT, 100AF, 3P, MCB 1 - 80AT, 100AF, 3P, MCB 2 - 60AT, 100AF, 3P, MCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet, Flush Mounted	1.00	set		
b.	Miscellaneous (cable ties, electrical tape, terminal lugs, etc.)	1.00	l.s		
1103 (1)	Lighting fixtures				
a.	Surface Mounted 32W - 1200x300mm Rectangle LED Light Panel	27.00	sets		
b.	25W, 230mm Ø, Surface Mounted LED Downlight (Daylight)	37.00	sets		
c.	40W, 60cm x 60cm, LED Panel (Daylight)	50.00	sets		
d.	8W, T5, LED Batten (Daylight)	47.00	sets		
e.	6W, Dual-Optic LED Emergency Light	24.00	pcs		
f.	20W, 8" x 8", Ceiling Mount Exhaust Fan (Modern Frame)	19.00	pcs		
1101 (2)	1 mm ² - 5.5 mm ² Electric Wire (TW/THHN/TWHN)				
a.	THHN wire No. 10 (Stranded) 5.5mm ²	3.00	box		
b.	THHN wire No.12 (Stranded - 3.5mm ²)	15.00	box		
c.	THHN wire No. 14 (Stranded - 2.0mm ²)	4.00	box		
d.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1101 (2)	8 mm ² - 22 mm ² Electric Wire (TW/THHN/TWHN)				
a.	THHN wire No. 2 (Stranded - 30mm ²)	40.00	meters		
b.	THHN wire No.6 (Stranded - 14mm ²)	36.00	meters		
c.	THHN wire No. 8 (Stranded - 8.0mm ²)	45.00	meters		
d.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1101 (2)	30 mm ² - 38 mm ² Electric Wire (TW/THHN/TWHN)				

a.	THHN wire No.500 (Stranded - 250mm ²)	44.00	meters		
b.	Miscellaneous (tie wire, electrical tape, etc.)	1.00	l.s		
1100	Junction/Utility/Pull/Square Box				
a.	Junction Box	114.00	pcs		
b.	Utility Box	144.00	pcs		
c.	Electrical Tape (Big)	23.00	pcs		
d.	Cable Tie 3x150mm	15.00	pack		
e.	Miscellaneous (torch, etc.)	1.00	l.s		
1100 (6)	15 mm ² - 32 mm ² - Polyvinyl Chloride (PVC) Pipes				
	a. PVC Pipe 1/4"Ø (25mmØ) including clamp and locknut	6.00	pcs		
	b. PVC Pipe 1/2"Ø (20mmØ) including clamp and locknut	1086.00	pcs		
	c. Miscellaneous (torch, etc.)	1.00	l.s		
1100 (6)	13 mm ² - 50 mm ² Polyvinyl Chloride (PVC) Pipe				
	a. PVC Pipe 1 1/4"Ø (40mmØ) including clamp and locknut	6.00	pcs		
	b. Miscellaneous (torch, etc.)	1.00	l.s		
1100 (1)	80mm ² dia. - 100 mm ² dia. Rigid Steel Conduit (RSC)/Intermediate metal Conduit (IMC)/Electrical Metal Tubing (EMT)				
	a. RSC Pipe 4"Ø (100mmØ) with coupling and clamp	7.00	pcs		
	b. Miscellaneous (tie wire, torch, etc.)	1.00	l.s		
1101	Duplex Convenience Outlet/Receptacle, Grounding Type (GT) I Weather Proof Duplex Convenience Outlet/Receptacle, Grounding Type (GT)I Special Purpose Convenience Outlet/Receptacle, Grounding Type for ACU, WH, etc./ Explosion Proof Type Duplex Convenience Outlet/Receptacle, Grounding Type (GT)I Duplex Convenience Outlet/Receptacle with Ground Fault Circuit Interrupter				
	a. Two Gang Universal Outlet with Ground with plate w/ Plate	84.00	pcs		
	b. Aircon Outlet with plate	12.00	pcs		
	c. Double Switch w/ Plate	32.00	pcs		
	d. Single Switch w/ Plate	35.00	pcs		

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
1200	Airconditioning and Refrigeration System				
a.	Supply and installation of 2.0 hp inverter type, wall mounted aircon including steel housing and complete accessories	12.00	set		
	TOTAL OF PART VII				

PART VIII	PLUMBING SYSTEM WORKS				
1001(8)	Installation of Polyvinyl Chloride (PVC) and other fittings				
	a. PVC PIPES (50mm D)	30.00	PC		
	b. PVC PIPES (101mm D)	100.00	PC		
	c. PVC 45deg. (3mm BEND x 101mm)	40.00	PC		
	d. PVC 87.5deg. (6mm BEND x 50mm)	95.00	PC		
	e. PVC 87.5deg. SINGLE BRANCH, SEEP, TEE (101mm x 101mm)	5.00	PC		
	f. PVC 45deg. SINGLE BRANCH, WYE (101mm x 101mm)	15.00	PC		
	g. PVC 45deg. SINGLE BRANCH, WYE (101mm x 50mm)	25.00	PC		
	h. PVC 45deg. SINGLE BRANCH, WYE (50mm x 50mm)	35.00	PC		
	i. BRASS CLEAN-OUT W/ PLUG & SEALING RING -(FLUSH) (50mm)	4.00	SET/S		
	j. BRASS CLEAN-OUT W/ PLUG & SEALING RING -(FLUSH) (101mm)	4.00	SET/S		
	k. PVC 87.5deg. SINGLE BRANCH, SEEP, TEE (101mm x 50mm)	5.00	PC		
	l. PVC 45deg. (3mm BEND x 50mm)	75.00	PC		
	m. PVC TEE (50mm D)	20.00	PC		
	n. PVC P-TRAP W/ PLUG & SEALING RING (50mm)	1.00	PC		
	o. PVC CONCENTRIC BUSHING REDUCER (101mm x 50mm)	20.00	PC		
	p. 1-1/2" Ø SS BOTTLE TRAP	17.00	SET/S		
	q. 1-1/2" Ø uPVC BOTTLE TRAP	11.00	SET/S		
	r. Miscellaneous (400cc solvent cement, teflon tape, sealant, etc.)	1.00	l.s		
1002(3)	Installation of Polypropylene Random Copolymer (PPR) and other fittings				
	a. 3/4" Ø x 4m, PN20, PPR PIPE	30.00	PC/S		
	b. 1/2" Ø x 4m, PN20, PPR PIPE	40.00	PC/S		
	c. 25mm x 25mm x 25mm TEE	10.00	PC/S		
	d. 25mm x 20mm x 25mm TEE	15.00	PC/S		
	e. 20mm x 20mm x 20mm TEE	30.00	PC/S		
	f. 25mm x 90° ELBOW	10.00	PC/S		
	g. 20mm x 90° ELBOW	45.00	PC/S		
	h. 25mm TEE THREADED	1.00	PC/S		
	i. 20mm TEE THREADED	37.00	PC/S		
	j. 20mm END CAP	37.00	PC/S		
	k. 25mm UNION PATENTE MALE	1.00	PC/S		
	l. 25mm COUPLING	5.00	PC/S		

	l. 20mm COUPLING	5.00	PC/S		
	m. 25mm x 20mm BUSHING	5.00	PC/S		
	n. 1/2", PN20, PPR STOP VALVE	23.00	PC/S		
	o. 3/4", PN20, PPR CHECK VALVE	2.00	PC/S		
q.	Miscellaneous (special fusion tool, marker, pipe cutter, sand paper, clean cloth, sleeves, etc.)	1.00	l.s		
1002(5)	Installation of Plumbing Fixtures				
a.	Dual-Flush, Elongated, One-Piece Water Closet including tank fitting, toilet bowl fastener and all other accessories and consumables	7.00	SET		
b.	Wall-Mount Urinal w/ Integral Trap including Lever type Flush Valve and all other accessories and consumables	1.00	SET		
c.	16 x 48 x 35", Scrub Sink - Double, 304 Stainless , Sink with 15" Deep, Stainless foot tube pedestal, with complete accessories	1.00	PC/S		
d.	500mm x 400mm x 200mm Undermount, Single-Bowl, SS Sink including SS Gooseneck Faucet accessories and consumables	17.00	SET/S		
e.	Half-Pedestal Lavatory w/ Integral Trap including SS Faucet, SS Angle Valve and all other accessories and consumables	6.00	PC/S		
f.	Round Vessel-Type Lavatory w/ Integral Trap including SS Vessel Faucet, SS Angle Valve and all other accessories and consumables	1.00	PC/S		

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
g.	10cm x 10cm Square, SS Invisible Floor Drain including consumables	11.00	PC/S		
h.	SS Wall-mount Soap Holder	7.00	PC/S		
i.	SS Wall-mount Tissue Holder	7.00	PC/S		
j.	SS Hand-Held Bidet Spray including SS wall-mount holder and all other accessories and consumables	7.00	PC/S		
k.	SS Wall-Mount Hose Bibb including accessories and consumables	2.00	PC/S		
l.	SS Grab Bar	3.00	PC/S		
m.	Wall Shower Head	1.00	PC/S		
n.	SS Wall-mount Shower Curtain Rod	2.00	PC/S		
o.	SS Wall-mount Towel Rack	1.00	PC/S		
p.	SS Emergency Eyewash and Shower Set: Rain-Type shower head, Hand Held shower w/ SS Hose and Slide Bar, plumbed eyewash, pop off cover, actuator including accessories and consumables	1.00	PC/S		
q.	30" x 36" Frameless Wall-mount Mirror including Mounting Clips	7.00	PC/S		
	TOTAL OF PART VIII				

PART IX	PAINTING WORKS				
1032(1)a	Painting works				
	b. CONCRETE NEUTRALIZER	5.00	LTR		
	c. CONCRETE PRIMER	60.00	GAL/S		
	d. PATCHING COMPOUND	90.00	KG/S		
	e. PAINT LATEX SEMI GLOSS	144.00	GAL		
	f. GLAZING PUTTY	4.00	GAL/S		
	g. FLAT WALL ENAMEL	5.00	GAL/S		
	h. QUICK DRY ENAMEL	7.00	GAL/S		
	i. THINNER PAINT	50.00	GAL		
	j. TINTING COLOR	3.00	PINT		
j.	Miscellaneous (Air brush, paint roller with tray, paint brush, tinting & acry colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
	TOTAL OF PART IX				
PART X	DOOR AND WINDOWS				
1006	Steel Doors and Frame with complete accessories				
a.	GA. 18 Aluminum Louvered Door on GA 16 50mm x 75mm baked powder coated with stainless barrel bolt and stainless steel handle and provide foot & chain bolts				
1	1 set/s - 1.4mW x 2.10mH; 4 Panel Steel Louvered Door; (1 Panel door 0.35mL x 2.10mH) Lockset: 2 unit/s C-type pull handle, 1 unit/s deadbolt, 8 pc/s heavy duty s/s hinges, and 1 pc/s s/s barrel bolt 3/4" x 12"	2.94	m ²		
	Location: GF - Waste holding area				
2	2 set/s - 1.2mW x 1.50mH; 2 Panel Steel Louvered Door; (1 Panel door 0.6mL x 1.50mH) Lockset: 4 unit/s C-type pull handle, 2 unit/s deadbolt, 16 pc/s heavy duty s/s hinges, and 2 pc/s s/s barrel bolt 3/4" x 12"	3.60	m ²		
	Location: 2ND FLR - Janitors Closet, 3RD FLR - Janitors Closet				
b	Plain Hollow Core Steel Door Matte finish on 50mm x 100mm steel door jamb, complete with accessories				
1	3 set/s - 1.20mW x 2.15mH Hollow Core Steel Door with wired glass side vision panel, 2 Panel door (0.8mL x 2.10mH; 0.4mW x 2.10mH) Lockset: 3 unit S/s Lever-type door knob, and 21 pc/s 3/4" heavy duty cylindrical hinges	7.56	m ²		
	Location: GF - Birthing Room, Ward, 2nd flr - Minor Surgical Room				
2	1 set/s - 0.90mW x 2.15mH Hollow Core Steel Door, Lockset: 1 unit S/s Lever-type door knob, and 8 pc/s 3/4" heavy duty cylindrical hinges	7.56	m ²		
	Location: GF - TB DOTS				

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
3	D2 - 1 set/s - 0.90mW x 2.10mH Fire Rated Door Lockset: 1 unit/s Emergency Exit Panic Device, 4 unit/s Heavy duty Cylindrical Hinges and 1 unit/s Self-closing hardware	1.89	m ²		
	Location: GF - Fire Exit Door				
d.	Miscellaneous (Air brush, paint roller with tray, paint brush, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1007	Aluminum Glass Door (Sliding Type/ Swing Type)				
a.	12mm thk Tempered clear glass on 50mm x 100mm analok aluminum frame on 50mm x 100mm analok aluminum door jamb, complete with accessories				
1	5 set/s - 1.6mW x 2.15mH Double Swing Glass Door; 1 Panel door (0.8mL x 2.10mH) with fixed glass transom (1.60mL x 0.40mH) Lockset: 10 unit/s C-type pull handle, 5 set locking mechanism (double finish round cylinder with lock case), 20 pc/s heavy duty pivot hinges and floor door lock	14.70	m ²		
	Location: GF - Main Entrance, Birthing Home Entrance, Ante-Room Entry, 2nd flr - PCF Entrance, 3rd flr - Clinical Laboratory Entrance				
b.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1008	Aluminum Glass Window (Sliding/ Casement / Awning/ Fixed Type)				
a.	AWNING TYPE STEEL CASEMENT WINDOWS	3.60	m ²		
1	3 set/s - 1.0mW x 1.20mH; 3 Panel Awning Window				
2	1 set/s - 0.80mW x 1.20mH; 3 Panel Awning Window				
3	4 set/s - 0.60mW x 0.50mH; 1 Panel Awning Window				
b.	SLIDING ALUMINUM WINDOW	37.04	m ²		
1	2 set/s - 1.80mW x 1.20mH; 2 Track Sliding Window				
2	5 set/s - 1.60mW x 1.20mH; 2 Track Sliding Window				
3	9 set/s - 1.20mW x 1.20mH; 2 Track Sliding Window				
c.	PASS THROUGH ALUMINUM WINDOW	1.20	m ²		
1	1 set/s - 1.0mW x 1.20mH; Fixed Glass with 0.2mH Pass Through Window				
d.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, painter's tape, etc.)	1.00	l.s		
1010(2)b	Wooden Panel Door				
a.	FLUSH TYPE SOLID CORE DOOR ON 50MM x 75MM WOODEN DOOR JAMB	10.08	m ²		
1	9 set/s - 0.90mW x 2.10mH - 1 Panel Solid Core Flush Door				
	Location: GF - Electrical Room, Consultation Room, 2nd - Prenatal Room, Post-consultation Room, Dental Room, Consultation Room, Adolescent Room, Lactation Room, 3rd - Collection Room				

2	6 set/s - 0.80mW x 2.10mH - 1 Panel Solid Core Flush Door				
	Location: GF - TB-DOTS, Sterilization Room, 3rd - Staff Pantry, Receiving Area, Storage Room, Sterilization Room				
b.	DOOR LOCKS (SCHLAGE OR EQUIVALENT)	15.00	SET		
c.	HINGE (50mm x 101mm)	45.00	PR		
d.	Miscellaneous (Air brush, sealant, tinting colors, stopa rugs, sand paper, etc.)	1.00	l.s		
1043	PVC Door and Frames with complete accesories				
a.	PVC DOOR ON 50MM x 75MM PVC DOOR JAMB	10.71	m ²		
	1 1 set/s - 0.90mW x 2.10mH PVC Door with louver				
	Location: GF - PWD CR				
	2 6 set/s - 0.70mW x 2.10mH PVC Door with louver				
	Location: GF - Staff Toilet, Ward T&B, 2nd flr - Staff Toilet and Patient Toilet, 3rd flr - Staff Toilet and Patient Toilet				
b.	DOOR LOCKS	7.00	SET		
c.	HINGE (50mm x 101mm)	21.00	PR		
d.	Miscellaneous (sealant, etc.)	1.00	l.s		
	TOTAL OF PART X				

Project Title: **Proposed Repair and Renovation of Kalayaan Health Center**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
PART XI	PROVISIONAL ITEMS				
1016	Waterproofing Cement Base				
b.	WATER PROOFING CEMENT	7.00	BAG		
Z.1	Provision of Epoxy Paint Finish				
a.	EPOXY PRIMER	0.50	GAL/S		
b.	EPOXY REDUCER	0.50	GAL/S		
c.	AQUA EPOXY	1.00	GAL/S		
d.	Miscellaneous (paint roller with tray, paint brush, tinting colors, stopa rugs, sand paper, etc.)	1.00	l.s		
Z.2	Provision of dismantling and reinstallation of existing cabinets				
a.	SEALANT	10.00	CRTG		
b.	Miscellaneous (caulking gun, sponge, caulk tool, painter's tape, etc.)	1.00	l.s		
Z.3	Provision of 12" Height SS Embossed Text Signage and 800mm Ø SS Embossed Circular Logo Signage				
a.	12" Height SS Embossed Text Signage	20.00	PC/S		

	(' KALAYAAN HEALTH CENTER ')				
b.	800mm Ø SS Embossed Circular Logo Signage (Pasay Health Department Seal)	1.00	PC/S		
c.	Miscellaneous (sealant, etc.)	1.00	l.s		
Z.4	Provision to refurbish the existing windows, such as resealing, replacement of locking mechanism and hinges	1.00	l.s		
Z.5	Provision to 38mm dia.stainless steel railings				
a.	Supply and installation of 38mm dia.stainless steel railings with complete accessories	16.00	l.m		
	Location: Facade				
	TOTAL OF PART XI				
PART XII	CABINETS WORKS				
1003(3)	Cabinets				
a.	Marine Plywood (1.2m x 2.4m x 19mm)	20.00	pc		
b.	Marine Plywood (1.2m x 2.4m x 6mm)	5.00	pc		
c.	Particle Board with laminates on 2 sides, 3/4" (19mm) x 4' x 8'	45.00	sheet/s		
d.	Bar, GI, Tubular, 1.2mm x 1" x 1" x 6m	5.00	pc/s		
e.	PVC 3/4" Edging	250.00	ln.m		
f.	2" x 4" x 10' s4s KD	20.00	pc		
g.	1" x 2" x 10' s4s KD	50.00	pc		
h.	1/2" x 1" x 10' s4s KD	50.00	pc		
i.	Handle door	180.00	pc		
j.	Soft Closed Concealed Hinges	360.00	pr		
i.	Wellwood Glue	20.00	gal		
j.	Assorted Common Wire Nails	15.00	kg		
k.	Concrete Nails (3")	15.00	kg		
l.	Sandpaper	3.00	roll		
m.	Miscellaneous (wood glue, nail, etc.)	1.00	l.s		
	TOTAL OF PART XII				
	GRAND TOTAL				

*Including all Direct and Indirect Cost per Items.