



**SUPPLEMENTAL/ BID BULLETIN NO. 1**

**IB2024 – 089E**

**Procurement of Proposed Repair and Renovation of San Isidro Health Center and Animal Bite Treatment Center**

This Supplemental/Bid Bulletin No. 1 is being issued to revise provisions/specifications in the Bidding Documents for a forecited project:

1. Query during Pre-bidding Conference:		
Technical Specifications	Query	Response of the End User Unit
List of contractor Key Personnel	Submission of different set of names in the list of Contractor's Personnel per project	Submission of different set of names in the list of Contractor's Personnel per project NOT GRANTED
List of Equipment -	Submission of different set of names of equipment per project	Submission of different set of names of equipment per project NOT GRANTED

Bidders are advised to use the **following attached forms and submit them together with all required documents for the submission of bids on the 25<sup>th</sup> day of October 2024, 9:00 AM:**

This Supplemental/Bid Bulletin No. 1 shall be integral to the Bidding Documents. All other provisions indicated in the bidding documents not affected by this Supplemental/Bid Bulletin No. 1 shall remain in effect.

For guidance and information of all concerned.

Issued this 18<sup>th</sup> day of October 2024 in MMCHD

Approved by:

  
**JEREMIAS FRANCIS Y. CHAN, MD**  
Licensing Officer V / BAC Chairperson

Republic of the Philippines  
Department of Health  
Metro Manila Center for Health Development

**TECHNICAL SPECIFICATIONS**

<b>Item No. 1</b>	<b>PROCUREMENT OF PROPOSE REPAIR AND RENOVATION OF SAN ISIDRO HEALTH CENTER AND ANIMAL BITE TRATMENT CENTER, PASAY CITY</b>	Qty./Unit	<b>1 LOT</b>		
<b>ABC: P4,997,671.15</b>					
<b>PURCHASER'S SPECIFICATION</b>				<b>STATEMENT OF COMPLIANCE</b>	
Project Title: <b>Proposed Repair and Renovation of San Isidro Health Center and Animal Bite Treatment Center</b>					
ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
	Location: 2nd Flr - Lactation Room, Collection Room				
b.	Salvageable Door - refurbishing of Solid Core Flush Door including removal and reinstallation, surface preparation, repainting using airbrush tool	15.75	m <sup>2</sup>		
1	1 set/s - 1.20mW Door with ( 0.40mW x 2.10mH and 0.80mW x 2.10mH) - 2 Panel Solid Core Flush Door				
2	7 set/s - 0.90mW x 2.10mH - 1 Panel Solid Core Flush Door				
c.	DOOR LOCKS	14.00	SET		
d.	HINGE (50mm x 101mm)	39.00	PR		
e.	Miscellaneous (Air brush, sealant,	1.00	l.s		

	tinting colors, stopa rugs, sand paper, etc.)				
1043	PVC Door and Frames with complete accesories				
a.	PVC DOOR ON 50MM x 75MM PVC DOOR JAMB	10.08	m <sup>2</sup>		
	1 4 set/s - 0.90mW x 2.10mH PVC Door with louver				
	Location: GF - SPUTUM COLLECTION, PWD CR, ABC - FEMALE AND MALE CR,				
	2 2 set/s - 0.60mW x 2.10mH PVC Door with louver				
	Location: GF - Staff Toilet and Janitors Closet, 2ND - PATIENTS TOILET, STAFF TOILET				
	3 2 set/s - 0.60mW x 2.10mH PVC Door with louver				
	Location: GF - Staff Toilet and Janitors Closet				
	b. DOOR LOCKS	6.00	SET		
	c. HINGE (50mm x 101mm)	18.00	PR		
	d. Miscellaneous (sealant, etc.)	1.00	l.s		
	<b>TOTAL OF PART XI</b>				
<b>PART XII</b>	<b>PROVISIONAL ITEMS</b>				
1016	Waterproofing Cement Base				
	l. WATER PROOFING	3.00	BAG		

	CEMENT				
Z.1	Provision of Epoxy Paint Finish				
a.	EPOXY PRIMER	1.00	GAL/S		
b.	EPOXY REDUCER	1.00	GAL/S		
c.	AQUA EPOXY	2.00	GAL/S		
d.	Miscellaneous (paint roller with tray, paint brush, tinting colors, stopa rugs, sand paper, etc.)	1.00	l.s		
Z.2	Provision of dismantling and reinstallation of existing cabinets				
a.	SEALANT	10.00	CRTG		
b.	Miscellaneous (caulking gun, sponge, caulk tool, painter's tape, etc.)	1.00	l.s		
Z.3	Provision to replacement the polycarbonate roofing sheet of Canopy and Roofing at Rear				
a.	STRUCTURAL STEEL TUBULAR BAR (A36)	172.00	KG		
b.	STRUCTURAL STEEL CHANNEL BAR (A36)	278.00	KG		
c.	STRUCTURAL STEEL PURLINS	375.00	KG		
d.	MILLED STEEL PLATES PLAIN FY36	51.00	KG		
e.	MACHINE BOLTS WITH NUTS AND WASHER	81.00	KG		
f.	TEK SCREW	110.00	PC		
g.	CORRUGATED ROOFING, GAUGE 26 (0.551 mm x 2.44m)	84.00	SQ.M		
h.	3.0MM THK X 4' X LN.FT. CLEAR	11.00	LN.FT.		

	POLYCARBONATE SOLID PANEL				
i.	PRE-PAINTED GUTTER, GA 24(0.701 MM) X 2.44m	17.00	LNM		
j.	PRE-PAINTED FLASHING, GA 24(0.701 MM) X 2.44m	29.00	LNM		
	c. Miscellaneous (sealant, cutting disc, welding rod, etc.)	1.00	l.s		
Z.4	Provision of 12" Height SS Embossed Text Signage and 800mm Ø SS Embossed Circular Logo Signage	1.00	L.S.		
a.	12" Height SS Embossed Text Signage	21.00	PC/S		
	(' SAN ISIDRO HEALTH CENTER ')				
b.	8" Height SS Embossed Text	25.00	PC/S		
	(' ANIMAL BITE TREATMENT CENTER ')				
c.	800mm Ø SS Embossed Circular Logo Signage (Pasay Health Department Seal)	1.00	PC/S		
d.	Miscellaneous (sealant, etc.)	1.00	l.s		

**Project Title: Proposed Repair and Renovation of San Isidro Health Center and Animal Bite Treatment Center**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>UNIT</b>	<b>UNIT COST</b>	<b>TOTAL COST</b>
Z.5	Provision of Steel Column for Comfort Room (ABC and HF) and Steel connection				
a.	GI PIPE SCHEDULE 40 DIA (102mm)	8.00	PC/S		
b.	MILLED STEEL PLATES PLAIN FY36	27.00	KG		
c.	MACHINE BOLTS WITH NUTS AND WASHER	53.00	KG		
d.	Miscellaneous (sealant, cutting disc, welding rod, etc.)	1.00	l.s		
	<b>TOTAL OF PART XII</b>				
<b>PART XIII</b>	<b>CABINETRY WORKS</b>				
1003(3)	Cabinets				
a.	Marine Plywood (1.2m x 2.4m x 19mm)	10.00	pc		
b.	Marine Plywood (1.2m x 2.4m x 6mm)	5.00	pc		
c.	Particle Board with laminates on 2 sides, 3/4" (19mm) x 4' x 8'	5.00	sheet/s		
d.	Bar, GI, Tubular, 1.2mm x 1" x 1" x 6m	4.00	pc/s		
e.	S4S KD Lumber 1" x 2" x 12ft	2.00	pc/s		
f.	PVC 3/4" Edging	40.00	ln.m		
g.	2" x 4" x 10' s4s KD	5.00	pc		
h.	1" x 2" x 10' s4s KD	10.00	pc		
i.	1/2" x 1" x 10' s4s KD		pc		

		30.00			
j.	Handle door	20.00	pc		
i.	Soft Closed Concealed Hinges	40.00	pr		
j.	Wellwood Glue	5.00	gal		
k.	Assorted Common Wire Nails	5.00	kg		
l.	Concrete Nails (3")	5.00	kg		
m.	Sandpaper	1.00	roll		
n.	Miscellaneous (wood glue, nail, etc.)	1.00	l.s		
	<b>TOTAL OF PART XIII</b>				
*Including all Direct and Indirect Cost per Items					