



SUPPLEMENTAL/ BID BULLETIN NO. 1

IB2024 – 081E

**Procurement for the Proposed Repair/Improvement of Maybunga Health Center
(Rebid)**

This Supplemental/Bid Bulletin No. 1 is being issued to revise provisions/specifications in the Bidding Documents for a forecited project:

1. Query during Pre-bidding Conference:		
Technical Specifications	Query	Response of the End User Unit
No changes as stipulated in the technical specification		

Bidders are advised to use the **following attached forms and submit them together with all required documents for the submission of bids on the 22nd day of August 2024, 9:00 AM:**

This Supplemental/Bid Bulletin No. 1 shall be integral to the Bidding Documents. All other provisions indicated in the bidding documents not affected by this Supplemental/Bid Bulletin No. 1 shall remain in effect.

For guidance and information of all concerned.

Issued this 13th day of August 2024 in MMCHD

Approved by:

JEREMIAS FRANCIS Y. CHAN, MD
Licensing Officer V / BAC Chairperson

Republic of the Philippines
Department of Health
Metro Manila Center for Health Development

TECHNICAL SPECIFICATIONS

Item No. 1	Proposed Repair/Improvement of Maybunga Health Center	Qty./Unit	1 Lot
Name of Manufacturer:			
Brand:			
ABC: 999,079.50			

PURCHASER'S SPECIFICATION	STATEMENT OF COMPLIANCE
---------------------------	-------------------------

Project:	Proposed Repair/ Improvement of Maybunga Health Center				
Location:	Calinao Compound, Brgy. Maybunga, Metro Manila				
Owner:	LGU OF PASIG				
Subject:	Detailed Unit Price Analysis				

ITEMIZED BREAKDOWN					
ITEM NO.	DESCRIPTION	QTY	UNIT	TOTAL COST	UNIT COST
PART I.	OTHER GENERAL REQUIREMENTS				
B.5 (1)	Project Billboard / Signboard	1.00	each		
B.7 (1)	Occupational Safety and Health Program	1.00	l.s.		
	TOTAL OF PART II			PhP -	
PART II.	CIVIL, MECHANICAL, ELECTRICAL, AND SANITARY / PLUMBING WORKS				
PART A	STRUCTURE EXCAVATION				
803(1)a	Structure Excavation (Common Soil)	15.50	cu.m.		
804(1)a	Embankment from Structure Excavation	13.95	cu.m.		
804(7)	Gravel Fill	1.50	cu.m.		

	TOTAL OF PART A			PhP	
				-	
PART B	SITE DEVELOPMENT				
807 (13)	Fence				
	Pipe, GI, 2" x 10', Sch.40	17.00	pc/s		
	Wire Mesh, Welded, 3.5mm dia x 2" x 2" x 6' x 20'	4.00	sheet/s		
	Bar, Flat, 2.25mm thk x 1" x 6m	44.00	pc/s		
	Consumables (Welding Rod, etc.)	1.00	lot		
807 (14)	Gate				
	Pipe, GI, 2" x 10', Sch.40	3.00	pc/s		
	Wire Mesh, Welded, 3.5mm dia x 2" x 2" x 6' x 20'	1.00	sheet/s		
	Bar, Flat, 2.25mm thk x 1" x 6m	5.00	pc/s		
	Fabricated Foot Bolt	2.00	pc/s		
	Locking Mechanism	2.00	pc/s		
	Consumables (Welding Rod, etc.)	1.00	lot		
	TOTAL OF PART B			PhP	
				-	
PART C	PLAIN AND REINFORCED CONCRETE WORK				
900 (1)	Structural Concrete for Footing Tie Beam, Column, Suspended Slab, Girder/Beam (Class A, 28 days)				
	Portland Cement	39.00	bags		
	Gravel - G1	4.50	cu.m.		
	Sand	2.50	cu.m.		
902 (1)a	Reinforcing Steel Bar (Deformed) Grade 40				
	Reinforcing Steel Bars Grade 40	259.00	kg.		
	G.I. Tie Wire # 16	6.00	kg.		
903 (1)	Formworks and Falseworks				

	TOTAL OF PART C			PhP	
				-	
PART D	FINISHINGS AND OTHER CIVIL WORKS				
1001(1)a	50mmØ-100mmØ PVC Pipe, Series 600/ Series 1000				
	Ø 50mm PVC (S1000)	4.00	pcs		
	Ø 50mm Tee	6.00	pcs		
	Ø 50mm Elbow	6.00	pcs		
	Consumables (Teflon Tape, Concrete Cement, etc.)	1.00	lot		
1001 (8)	Sewer Line Works				
	Ø 100mm PVC (S1000)	4.00	pcs		
	Ø 100mm Tee	1.00	pcs		
	Ø 100mm Elbow	6.00	pcs		
	Ø 100mm Wye	2.00	pcs		
	Consumables (Teflon Tape, Concrete Cement, etc.)	1.00	lot		
1001(9)	Storm Drainage and Downspout				
	Pipe, PVC, 3" x 10', Orange	8.00	pcs		
	Consumables (Teflon Tape, Concrete Cement, etc.)	1.00	lot		
1002(5)	Wall Hung/Countertop/Under Counter Lavatory with Complete Accessories				
	Half-Pedestal Lavatory w/ Integral Trap including SS Faucet, SS Angle Valve and all other accessories and consumables	2.00	set		
1003(1)	4.5mm Fiber Cement Board/ 4.5 mm Marine Plywood/ 6 mm Marine Plywood/ 6mm Ordinary Plywood on Metal Frame Ceiling				
	Fiber Cement Board, 1/4" (6mm) x 4' x 8'	2.00	sheet/s		
	2" x 250' Fiberglass Mesh Tape	1.00	roll/s		
	Rivets (500s)	0.50	box/es		

	Consumables (Black Screw, etc.)	1.00	lot		
1003(2)	4.5mm 6.0 mm Fiber Cement Board 4.5mm 6.0 mm 4' X 8' thk fiber cement board 4.5mm Marine Plywood/6.0 mm Marine Plywood/6.0 mm Ordinary Plywood on Metal Frame Double Wall Partition				
	0.5mm thick, 77mm x 28mm x 3m Metal Tracks	7.00	pc/s		
	.5mm thick, 75mm x 32mm x 3m Metal Studs	12.00	pc/s		
	Fiber Cement Board, 1/4" (6mm) x 4' x 8'	13.00	sheet/s		
	Dyna (Expansion) Bolt, 3/8" dia. x 70mm	10.00	pc/s		
	Rivets (500s)	0.50	box/es		
	2" x 250' Fiberglass Mesh Tape	2.00	roll/s		
	Consumables (Black Screw, etc.)	1.00	lot		
1005	Residential Casement Steel Windows Heavy Duty Side-hinged Ventilator Projected Ventilator/ Awning Ventilator/ Grille Window				
	Bar, Flat, 3.25mm thk x 1 1/2" x 6m	14.00	pc/s		
	Bar, Angle, 4mm x 1 1/2" x 1 1/2" x 6m	14.00	pc/s		
	Wire Mesh, Welded, 4.5mm dia x 2" x 2" x 6' x 20'	2.00	sheet/s		
	Consumables (Welding Rod, etc.)	1.00	lot		
1008	Aluminum Glass Window (Sliding/ Casement/ Awning/ Fixed Type)				
	W-1, 1600 x 1200mm Sliding Type Window w/ 6mm thk. Powder Coated White, Alum. Frame	3.00	set/s		
	W-2, 600 x 1200mm Transaction Window Counter w/ 6mm thk. Powder Coated White, Alum. Frame	1.00	set/s		
1010(2)b	Wooden Panel Door				

	D1, 3set/s - 800 x 2100 World Champion Masonite (HDF) Solid Core Zen Series Design w/ 5mm Vertical Groove in Elegance Fine-Grained Skin on a 50 x 150mm thk KD wd Jamb including 4 - 4 x 4 Loose Pin Hinges & Cyindrical Knob set Surelock Series 300	3.00	set/s		
1013 (2)c	Fabricated Metal Roofing Accessory (Gutter)				
	Gutter (0.6mm)	22.00	m		
	12" x 1" Plain GI Strap	25.00	pcs		
	Blind Rivets	50.00	pcs		
	Consumables (Sealant, etc.)	1.00	lot		
1021 (3)	Floor Topping				
	Portland Cement	27.00	bags		
	Gravel - G1	3.50	cu.m.		
	Sand	2.00	cu.m.		
1027 (1)	Cement Plaster Finish				
	Portland Cement	6.00	bags		
	Fine Aggregate	1.00	cu.m.		
1032(1)a	Painting Works (Masonry Painting)				
	Flat Latex Paint	20.00	gal/s		
	Semi-Gloss Latex Paint	20.00	gal/s		
	Masonry Putty	7.00	gal/s		
	Concrete Neutralizer	4.00	gal/s		
	Patching compound	4.00	kg/s		
	Consumables (Stopa Rug, Paint Brush, Paint Roller, etc)	1.00	lot		
1032(1)c	Painting Works (Metal Painting)				
	Quick Dry Enamel as Top Coat	12.25	gal/s		
	Red Oxide Metal Primer	4.25	gal/s		

	Paint Thinner	4.25	gal/s		
	Metal Etching Solution	4.25	gal/s		
	Consumables (Stopa Rug, Paint Brush, Paint Roller, etc)	1.00	lot		
1046 (2)a2	CHB Non Load Bearing (including Reinforcing Steel), 150mm THK.				
	150 mm thk CHB (Non-Load Bearing)	343.00	pcs.		
	Portland Cement	42.00	bags		
	Fine Aggregate	2.50	cu.m.		
	Reinforcing Steel	73.00	kgs.		
	G.I. Tie Wire # 16	1.00	kgs.		
	TOTAL OF PART D			PhP	-
PART E	ELECTRICAL (ROUGH-IN)				
1101	NEMA I (Enclosed Circuit Breaker) Single Phase or Three Phase Commercial/Industrial Type / Installation of Panel Boards and Manual Transfer Switch				
	Main Distribution Panel - MDP MAIN: 125AT, 200AF, 2P MCCB, 36kAIC Thermal Magnetic and Electronic Trip BRANCH: 1 - 100AT, 100AF, 2P, 25kAIC, MCCB 1 - 60AT, 100AF, 2P, 18kAIC, MCCB In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet #16, Surface Mount	1.00	set		
	Mechanical Panel (PB-Mechanical) MAIN: 100AT, 100AF, 2P MCCB, 36kAIC Thermal Magnetic and Electronic Trip BRANCHES: 1 - 40AT, 100AF, 2P, 10kAIC, MCCB, TM Trip 9 - 30AT, 100AF, 2P, 10kAIC, MCCB, TM Trip In NEMA 1 Enclosure, Bolt-on with grounding Terminal Block, Powder Coated Finished, G.I. Sheet #16, Surface Mount	1.00	set		

	Enclosed Circuit Breaker (ECB-Main) 125AT, 200AF, 2P 18kAIC, MCCB, Common Trip, In Enclosure Bolt-on Type with grounding, Terminal Block, Powder Coated Finished, G.I. Sheet #16, Mounted with nameplates on Panel Board Bottom Lock and Keys	1.00	set		
	Enclosed Circuit Breaker (ECB- Genset) 60AT, 100AF, 3P 18kAIC, MCCB, Common Trip, In Enclosure Bolt-on Type with grounding, Terminal Block, Powder Coated Finished, G.I. Sheet #16, Mounted with nameplates on Panel Board Bottom Lock and Keys	1.00	set		
	Enclosed Circuit Breaker (ECB- AC) 30AT, 100AF, 2P 10kAIC, MCCB, Common Trip, In Enclosure Bolt-on Type with grounding, Terminal Block, Powder Coated Finished, G.I. Sheet #16, Mounted with nameplates on Panel Board Bottom Lock and Keys	1.00	set		
1102	Electrical Roughing-ins				
	38.0mm ² THHN Stranded Wire	70.00	li.m		
	30.0mm ² THHN Stranded Wire	16.00	li.m		
	14.0mm ² THHN Stranded Wire	40.00	li.m		
	8.0mm ² THHN Stranded Wire	43.00	li.m		
	5.5mm ² THHN Stranded Wire	20.00	li.m		
	3.5mm ² THHN Stranded Wire	300.00	li.m		
	2.0mm ² THHN Stranded Wire	150.00	li.m		
	32mm ⁴ (1" dia) RSC Pipe x 10ft. Sch 40	2.00	pcs		
	32mm ⁴ (1" dia) PVC Pipe x 10ft. Sch 40	14.00	pcs		
	20mm ⁴ (1/2" dia) PVC Pipe x 10ft. Sch 40	50.00	pcs		
	Hangers, supports, and accessories. Including angle bar, clamp, full thread, screws, bolts and nuts, flat washer, hauling, installation using scaffolding or ladder	10.00	sets		
	32mm ⁴ (1" dia) Service Entrance Cap,	2.00	pcs		

	Diecast Aluminum, Threaded type				
	Ground rod including ground clamp, 20mm dia x 3000mm dia solid G.I. steel with copper cladding	1.00	pcs		
	Ova eyebolt with 5/8 x 18", 1-1/2 eye inside diameter x2' with square nut	1.00	pcs		
	G.I. wires#16	1.00	klms		
	Electrical tape (Big)	1.00	rolls		
	Rubber tape	2.00	rolls		
	PVC Solvent, 1 Liter	1.00	cans		
	Wet and Dry Sealant, 200mL	1.00	cans		
	Elastomeric sealant, 1L,	1.00	cans		
	Junction box with grounding terminal lug, deep type, G.I. Gauge #16	33.00	pcs		
	Utility box with grounding terminal lug, deep type, G.I. Gauge #16	17.00	pcs		
1103	Installation of Lighting Fixtures, Switches and Outlets				
	Surfaced Type Luminaire, Housing made of sheet, powder coated in white resins, parabolic mirrorized aluminum reflector and multi-line satin finished louvers, 2 x 18 watts LED lamp, 30t' - 40t' burning hours	5.00	sets		
	LED panel Downlight. 12W, Daylight, Indoor Type, Recessed Type, 120 Lumens	10.00	pcs		
	Weatherproof Lighting Fixture, polycarbonate hsg, with , 2 x 9 watts LED lamp, 30t' - 40t' burning hours	5.00	pcs		
	Surfaced Type Luminaire, Housing made of sheet, powder coated in white resins, parabolic mirrorized aluminum reflector and multi-line satin finished louvers, 2 x 9 watts LED lamp, 30t' - 40t' burning hours	3.00	pcs		
	Duplex Outlet, 16A rating with grounding universal type cover plate, wide type, white	8.00	pcs		

	One Gang Switch, 10A Rating, with cover plate, wide type, white	3.00	pcs			
	Orbit Fan 16" diameter	10.00	pcs			
	Two Gang Switch, 10A Rating, with cover plate, wide type, white	6.00	pcs			
	TOTAL OF PART E			PhP		
	GRAND TOTAL			PhP		